

This drawing is supplied as a General Layout showing relative positions of main components and Guardian Industrial Doors Ltd accepts no responsibility for accuracy until a Site Survey has been undertaken.


If the End Plates and Barrel are within a False Ceiling or Soffit a Full Width Access Panel is required. (by others)

| Fixing To:- |                                |
|-------------|--------------------------------|
| Steel       | M8/M10 Set Screws              |
| Brick       | M8/M10 Rawbolts/Sleeve Anchors |
| Blockwork   | M8/M10 Rawbolts/Sleeve Anchors |
| Timber      | M8/M10 Coach Screws            |
| Concrete    | M8/M10 Rawbolts                |

The Client is responsible for making sure that the structure is capable of withstanding the weight of the shutter and suitable fixing points are available for the End Plate and Guide support channel.


The chart below shows the weight for a shutter with a maximum structural clear opening of 4400mmW x 2525mm H

|                 | Weights (kg) |
|-----------------|--------------|
| Barrel          | 43           |
| Curtain         | 78           |
| End Plates      | 6            |
| Guides          | 22           |
| Angles/Channels | 0            |
| Motor/HCG       | 10           |
| Safety Brake    | 5            |
|                 | 164          |




Elevation from Inside

Section on 'X-X'



Plan at Barrel Level



Plan at Guide Level

**GUARDIAN**  
DOOR SOLUTIONS FOR ALL REQUIREMENTS

45 Progress Rd,  
Leigh on Sea, SS9 5PR  
Tel: +44(0)1702 512424  
Fax: +44(0)1702 260117  
www.guardiandoors.com

UNLESS OTHERWISE INDICATED  
ALL DIMENSIONS IN MILLIMETERS  
AND ALL TOLERANCES ±1.0

|       |       |       |          |         |
|-------|-------|-------|----------|---------|
| DRAWN | CHK'D | APP'D | DATE     | SCALE   |
| MB    |       |       | 11/02/09 | 1:20@A3 |

TITLE  
**APHRODITE 9000 TUBE MOTOR FACE FIX.**  
4550mm O/A W x 2800mm O/A H Max.

Drwg No: APHRODITE 9000/250  
Guardian maintains a policy of progressive design and we reserve the right to modify specifications without prior notice or alteration to this drawing

|       |          |       |
|-------|----------|-------|
| ISSUE | DATE     | APP'D |
| 1     | 11/02/09 | PN    |